BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT41597

APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/01/2020-21, Date: 05.05.2020

Name of Work: Maintenance of water supply works to existing borewells at at Rachenahalli Village Surrounding area in Ward No. 06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
1	3500	Labour Charges of lifting of non functioning submersible Pump set along with cable and GI Pipes (BWSSB SR 14-15, P-558 I-1(i)	Each	114.4	Rupees One Hundred Fourteen and Forty Paise
2	35	Transportation of pumping machineries (P. 56 / I. 10.3.19) PRED SR (2012-13)	Each	944.55	Rupees Nine Hundred Forty Four and Fifty Five Paise
3	6	A)Rewinding of Submersible Pump Sets (BWSSB SR 14-15 P-58 I-A) 10 HP	No	5021.86	Rupees Five Thousand Twenty One and Eighty Six Paise Only
4	8	(BWSSB SR 14-15 P-58 I-A) 7.5 HP	No	4011.19	Rupees Four Thousand Eleven and Nineteen Paise Only
5	10	(BWSSB SR 14-15 P-58 I-A) 12.5 HP	No	6176.31	Rupees Six Thousand One Hundred Seventy Six and Thirty One Paise Only
6	11	(BWSSB SR 14-15 P-58 I-A) 15.0 HP	No	6087.1	Rupees Six Thousand Eighty Seven and Ten Paise Only
7	175	B) Replacement of Motor Parts: Pump Bowls (BWSSB SR 14-15 P-58 I-B)	No	323.25	Rupees Three Hundred Twenty Three and Twenty
8	35	Intermediate Piece (I.P) With IP Leaded Bronxe bush (BWSSB SR 14-15 P-58 I-B2)	No	750.39	Rupees Seven Hundred Fifty and Thirty Nine Paise Only
9	35	Upper Flange (BWSSB SR 14-15 P-59 I-C3)	No	346.34	Rupees Three Hundred Forty Six and Thirty Four Paise Only
10	35	Lower Housing (BWSSB SR 14-15 P-59 I-C4)	No	565.68	Rupees Five Hundred Sixty Five and Sixty Eight Paise Only
11	130	Guide vane (BWSSB SR 14-15 P-58 I-B5)	No	202.03	Rupees Two Hundred Two and Three Paise Only
12	35	Impeller Shell moulded with aluminium Bronze) (BWSSB SR 14-15 P-58 I-B6)	No	277.07	Rupees Two Hundred Seventy Seven and Seven
13	40	Discharge outlet (D.O) Bearing D.O Steel Bush P. (BWSSB SR 14-15 P-58 I-B7)	No	548.36	Rupees Five Hundred Forty
14	35	Pump shaft made out of stainless steel Centreless ground with key way (upto 8 stages) (BWSSB SR 14-15 P-58 I-B10)	No	692.67	Rupees Six Hundred Ninety
15	35	Pump Couping (Stainless Steel) (BWSSB SR 14-15 P-58 I-B12)	No	357.88	Rupees Three Hundred Fifty Seven and Eighty
16	80	Stud and Nuts (BWSSB SR 14-15 P-59 I-C8)	Each	92.36	Rupees Ninety Two and Thirty Six
17	20	Motor Base With Pin (BWSSB SR 14-15 P-59 I-C11)	Each	427.15	Rupees Four Hundred Twenty Seven and Fifteen

Signature of the contractor

10/07

10/07 Executive Engineer

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
18	20	Starter (with one year Guarantee) P No. 55 / I No. 10.3.3 PRED SR (2012-13)	No	5299.98	Rupees Five Thousand Two Hundred Ninety Nine and Ninety Eight Paise Only
19	25	Rotor (with one year Guarantee) P No. 55 / I No. 10.3.6) PRED SR (2012-13)	No	4932.65	Rupees Four Thousand Nine Hundred Thirty Two and Sixty Five Paise Only
20	35	Carbon Housing P. No. 56 / I No.10.3.12 PRED SR (2012-13)	No	498.51	Rupees Four Hundred Ninety
21	35	Thrust bearing block assembly complete with Segment bearing pad.P. No. 55 / I No.10.3.13 PRED SR (2012-13)	No	1206.93	Rupees One Thousand Two Hundred Six and
22	35	Oil Seal P. No. 54 / I No.10.2.3 PRED SR (2012-13)	No	131.19	Rupees One Hundred Thirty One and Nineteen Paise
23	35	Oil Seal Steel Bush P. No. 54 / I No. 10.2.4 PRED SR (2012-13)	No	157.43	Rupees One Hundred Fifty Seven and Forty Three Paise Only
24	40	D.O Bearing P. No. 44 / I No. 10.2.7 PRED SR (2012-13)	No	299.11	Rupees Two Hundred Ninety Nine and Eleven
25	160	Steel Bush P. No.55 / I No. 10.2.9 PRED SR (2012-13)	No	157.43	Rupees One Hundred Fifty Seven and Forty
26	95	Allen Screw P. No.44 / I No. 10.2.9 RDPR SR (2012-13)	No	26.24	Rupees Twenty Six and Twenty
27	25	Pump Key (Stainless Steel) P. No. 45 / I No. 10.2.11 RDED SR (2012-13)	No	131.19	Rupees One Hundred Thirty One and Nineteen Paise
28	20	Non – return valve (NRV) assembly complete with rubber 'O' Ring P. No. 55 / I No. 10.2.14 PRED SR (2012-13)	No	1416.83	Rupees One Thousand Four Hundred Sixteen
29	35	Cable Guard P. No. 55 / I No. 10.2.15 PRED SR (2012-13)	No	157.43	Rupees One Hundred Fifty
30	35	Strainer P. No. 45 / I No. 10.2.15 RDED SR (2012-13)	No	157.43	Rupees One Hundred Fifty
31	35	Brass Filter P. No. 55 / I No. 10.2.17 PRED SR (2012-13)	No	262.38	Rupees Two Hundred Sixty Two
32	35	Labour Chargesw (Over Hauling Only) P. No. 45 / I No. 10.2.18 PRED SR (2012-13)	No	583.52	Rupees Five Hundred Eighty
33	35	Re-erection charges of pumping machineries including overhauling and pointing P. No. 56 / I No. 10.3.20 PRED SR (2012-13)	Each	997.03	Rupees Nine Hundred Ninety Seven and Three
34	40	Lock Ring P. No. 45 / I No. 10.3.11 PREC SR (2012-13)	Each	89.21	Rupees Eighty Nine and Twenty One Paise Only
35	35	a) Carbon Housing P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	498.51	Rupees Four Hundred Ninety Eight and Fifty One
36	25	Top Carbon/Ferrodo padding P. No. 46 / I No. 10.3.12 APRDED SR (2012-13)	Each	157.43	Rupees One Hundred Fifty Seven and Forty
37	30	Bearing (Gunmetal) Centrifugal) Cast Aluminium Bronxe, Beaing bush P. No. 46 / I No. 10.3.16 APRDED SR (2012-13)	Each	419.8	Rupees Four Hundred Nineteen and Eighty Paise
38	40	Circillps P. No. 45 / I No. 10.3.17 PREC SR (2012-13)	Each	52.48	Rupees Fifty Two and Forty Eight Paise Only

Signature of the contractor

10/02

Executive Engineer

Sl. No	Approved Qty.	Description	Unit	Approved Tender Rates of S Narayana Rao ( )	
				In Figures	In Words
39	90	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete.... P No. 32/I No 3b KPWD Electrical SR 2010-11	No	157.43	Rupees One Hundred Fifty Seven and Forty Three Paise Only
40	1400	Threading of GI Pipes 50mm Dia P. No. 15 / I No.3.11.6 PRED SR (2012-13)	No	26.24	Rupees Twenty Six and Twenty Four Paise Only
41	1200	Supplying of submersible pump cable 1X3X6..0 Sq.mm (Page No. XLVII, Sl NO. 8, PWD SR-2018-19	Mtr	151.13	Rupees One Hundred Fifty One and Thirteen Paise Only
42	30	Supplying and fixing MCB (P.NO - XLVII, SL.NO - 19, PWD SR 18-19)	No	944.55	Rupees Nine Hundred Forty Four and Fifty Five Paise Only
43	239.63	Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in Ordinary soil not exceeding 1.5 m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m after breaking of clods complete as per specifications (P.NO - 6, I.NO - 2.3, PWD SR 18-19)	Cum	332.63	Rupees Three Hundred Thirty Two and Sixty Three Paise Only
44	710	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 96, I.NO - 13.73.2, PWD SR 18-19)	Mtr	413.84	Rupees Four Hundred Thirteen and Eighty Four Paise Only
45	239.63	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 7, I.NO - 2.11, PWD SR 18-19)	Cum	134.61	Rupees One Hundred Thirty Four and Sixty One Paise Only
46	10	Supplying & delivery of brand 50mm Gate Valve. (PWD SR 18-19, P.NO.XLVII Sl.no, 15	No	1889.1	Rupees One Thousand Eight Hundred Eighty Nine and Ten Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
10/07